

01



PLANNING YOUR CABIN

AFTER COMPLETING THE BUILD PLANNING PACKET YOU WILL HAVE A COST ESTIMATE.

PAY 25% OF THE DOWN PAYMENT TO APPROVE THE PROJECT. THIS STARTS THE PRODUCTION OF YOUR CABIN.

THE REMAINING BALANCE WILL BE DUE PRIOR TO DELIVERY.

02



*THIS STEP IS THE CUSTOMER'S RESPONSIBILITY. HOWEVER, WE CAN REFER CONTRACTORS TO HANDLE THIS STEP FOR YOU.

PREPARING THE SITE

TIME TO PREPARE THE CABIN FOUNDATION. THERE ARE TWO OPTIONS TO CONSIDER:

OPTION 1 CONCRETE FOUNDATION

MUST BE 3-6 INCHES WIDER THAN THE CABIN'S FOOTPRINT & 4-6 INCHES DEEP.

OPTION 2 GRAVEL / PATIO BLOCKS

MUST BE 3-6 INCHES WIDER THAN THE CABIN'S FOOTPRINT & 4 INCHES DEEP WITH ENOUGH PAVERS FOR ALL THE FOUNDATION POSTS.

03



"DRY IN" INSTALLATION

TYPICAL DRY-IN INSTALLATION IS 5-7 WORKING DAYS. THE INCLUDED/EXCLUDED LIST SHOWS THE MATERIALS USED.

ITEMS COMPLETED IN THIS STEP ARE:

WALLS

WINDOWS

ROOF

GUTTERS

IF A DIY INSTALLATION, COMER WILL GUIDE YOU THROUGH THE PROCESS.

04



FINISHING INSTALLATION THE OWNER TAKES OVER

AT THIS POINT, YOU WILL FINISH THE INSIDE TO CREATE A COZY AND FUNCTIONAL CABIN. INQUIRE ABOUT FURNITURE OPTIONS BEFORE OR AFTER YOUR CABIN IS BUILT.

